FRENCH ROCKS DIVISION.

The 22nd February 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks Division, up to 10th March 1898, for restoring the Nittur tank, Registered No. 43 of Malvalli taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st December 1898.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 8 A. M. and 5-30 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Nittur tank;" in default of which, tenders will be rejected.

5. The first acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	*Unit of work.*	
Bund—		
Earthwork including watering, tamping, &c.	C. yd.	8,300
Turfing rear and front slopes	Sqr.	771·94
Bench mark stones	Each.	2
Refixing the present grade stones	Do	32
Registered number stones	Do	1
Date stone	Do	1
Gauge stone	Do	1
New stone revetment	C. yd.	1,766
Old do	Do	2,490
Sluice—		
Constructing front and rear cisterns and other sundry repairs	Lump sum Rupees.	
Waste weir, left extension—		
Excavation	C. yd.	470
Brick in surki	C. ft.	488
Plastering with surki	Sqr.	1·59
Rough stone work new	C. yd.	170
Burnt stone slabs dressed	S. ft.	90
Baling	Lump sum Rupees.	
Improving and raising the existing left waste weir—		
Brick in surki	C. ft.	326
Burnt stone slabs dressed	S. ft.	288
Plastering with mortar	Sqr.	5·70
Wedging up the old apron	Lump sum Rupees.	
Waste weir, right—		
Repairing the right waste weir	Lump sum Rupees.	
Distribution—		
Constructing an aqueduct across the left Kodihalla to irrigate the lands marked yellow on the Revenue Survey Tracing	Lump sum Rupees.	

D. SITARAMA RAO, *Executive Engineer.*